

Batheaston Park /Secret Garden

Please find the attached Quotation for works described below.

Please note ...all our work is completed to high standards and completed by polite qualified tradesmen, which carry the full necessary insurance.

Reference available on request and you are welcome to come view any of are work we have completed in the past, by appointment.

Job Description

Fence off a section of car park and install temporary anti climb fencing (this will allow safe storage area for spoil and materials during the duration of our works.

Cover the carpark storage section with boards to prevent car park damage

Excavate total area of 600 sq meters to a depth of 150mm and remove spoils , this depth this will allow 100mm depth of type one and 50mm of Breeden golden amber self binding gravel.

600 total sq meters includes all the orange and yellow paths and areas designated on the key plan supplied by Batheaston council.

Remove spoils /.. we will use a grab hire method , therefore spoils will be removed from the designated storage area with in the car park.

Install type one base with accordance to Breeden aggregates specification and guide plan.

All type one base be compacted using the appropriate compaction machine.

Type one to be laid on top of 100- geotextile membrane.

Remove step level changes that currently lead too buxuas sepervirens planting, instead install a comfortable ramped access using golden gravel as the finish surface.

Install path edging tobermore retro 60mm paving , the paving will be bedded on top of the compacted type one base . (610 running meters in total)

All pavers to be concrete in place using cement and sharp sand 5-1 mix.

Install Breeden Golden amber gravel on top of the type one – this will be the finished material for all paths and designated areas.

All type one and golden amber gravel will be laid with the correct cross falls and gradients supplied within Breeden aggregates guidelines.

The sites and car park will be left clean and tidy

I will need provided from council the following

- all vegetation removed from pathway edging and designated areas with in the orange and yellow lines.

Water supply for wetting the binding gravel

Electric supply

We would like the park closed and the car park storage area available to us for three wks from the start of works.

Week one full excavation soil removal

Week two type one installation and edging laying

Week three Breeden path gravel installation and tidy of site.

Any questions please call

Kind regards

ashley rich TEL 01225 744849 / 07943492233